Name of the Work:	Engaging Gang mens, Silt & Tractor in Bagalagunte Ward No.14

CERTIFICATE

We Cetified that Sri. K.P.Umesh, Asst.Engineer and Sri.Vijayakumar.T.D Asst.Exe.Engineer have Personally visited the spots and prepare the Estimate in safe and economical using the schedule rate of PWD Bangalore Circle Banglore. during the Year 2018-19

Asst.Engineer
ward No 14

Asst.Exe.Engineer
T.Dasarahalli Sub Division

Scanned by CamScanner

Name of the work : Engaging Gang mens, Silt & Tractor in Bagalagunte Ward No.14

ಅಂದಾಜಿಗೆ ವರದಿ

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ, ದಾಸರಹಳ್ಳಿ ವಲಯ ವ್ಯಾಪ್ತಿಯ ಬಾಗಲಗುಂಟೆ ವಾರ್ಡ್ ನಂ.14ರ ವ್ಯಾಪ್ತಿಯ ಬಡಾವಣೆಗಳ ಚರಂಡಿಗಳಲ್ಲಿ ಹೂಳು ತುಂಬಿದ್ದು, ಚರಂಡಿಯಲ್ಲಿ ನೀರು ಸರಾಗವಾಗಿ ಹರಿಯದೇ ರಸ್ತೆಯ ಮೇಲ್ಭಾಗದಲ್ಲಿ ಹರಿಯುವುದರಿಂದ ಸಾರ್ವಜನಿಕರಿಗೆ ಹಾಗೂ ವಾಹನ ಸಂಚಾರಕ್ಕೆ ತೊಂದರೆಯಾಗುತ್ತಿರುತ್ತದೆ. ಆದ್ದರಿಂದ ಚರಂಡಿಯ ಮೇಲ್ಭಾಗದ ಸ್ಯ್ಯಾಬ್‌ಗಳನ್ನು ತೆಗೆದು ಚರಂಡಿಯಲ್ಲಿ ತುಂಬಿರುವ ಹೂಳನ್ನು ತೆಗೆಯಲು ಕೂಲಿಯಾಳುಗಳು, ಟ್ರ್ಯಾಕ್ಟರ್, ಜೆ.ಸಿ.ಬಿಗಳನ್ನು ಉಪಯೋಗಿಸಿಕೊಂಡು ಕಾಮಗಾರಿ ನಿರ್ವಹಿಸಲು ಈ ಅಂದಾಜಿನಲ್ಲಿ ಉದ್ದೆಶಿಸಲಾಗಿದೆ.

ಮುಂದುವರೆದಂತೆ 2018–19ನೇ ಸಾಲಿಗೆ ವಾರ್ಷಿಕ ಕಾರ್ಯಕ್ರಮ ಪಟ್ಟಿಯ ರೂ.300.00 ಲಕ್ಷಗಳಲ್ಲಿ ಮೀಸಲಿಡಲಾದ ರೂ.40.00 ಲಕ್ಷಗಳನ್ನು ಬಾಗಲಗುಂಟೆಯ ವಿವಿಧ ಬಡಾವಣೆಯ ರಸ್ತೆಗಳ ಚರಂಡಿಯಲ್ಲಿ ತುಂಬಿರುವ ಹೂಳನ್ನು ತೆಗೆಯಲು ಈ ಅಂದಾಜಿನಲ್ಲಿ ಉದ್ದೇಶಿಸಲಾಗಿದೆ.

ಅಂದಾಜಿನಲ್ಲಿ ಈ ಕೆಳಕಂಡ ಅಂಶಗಳನ್ನು ಅಳವಡಿಸಿಕೊಳ್ಳಲಾಗಿದೆ.

1. ಜೆ.ಸಿ.ಬಿ ಉಪಯೋಗಿಸುವುದು
2. ಟ್ರ್ಯಾಕ್ಟರ್ ಉಪಯೋಗಿಸುವುದು
3. ಕೂಲಿಯಾಳುಗಳನ್ನು ಉಪಯೋಗಿಸುವುವದು

. ಕವರಿಂಗ್ ಸ್ಲ್ಯಾಬ್ ಅಳವಡಿಸುವುದು (ಆರ್.ಸಿ.ಸಿ)

ಇತ್ಯಾದಿ ಮುಂತಾದ ಅಂಶಗಳನ್ನು ಅಳವಡಿಸಿಕೊಂಡು ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ ಬೆಂಗಳೂರು ವೃತ್ತ ಕಛೇರಿಯ ದರಪಟ್ಟಿಯಂತೆ 2018–19ನೇ ಸಾಲಿಗೆ ರೂ.40.00 ಲಕ್ಷಗಳಿಗೆ ಅತೀ ಸೂಕ್ಷ್ಮ ಸರಳತೆ ಅನುಸರಿಸಿ ಅಂದಾಜನ್ನು ತಯಾರಿಸಿ ಅಂದಾಜಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಹಾಗೂ ತಾಂತ್ರಿಕ ಅನುಮೋದನೆಯನ್ನು ನೀಡಲು ಕೋರಲಾಗಿದೆ.

ಸಹಾಯಕ ಅಭಿಯಂತರರು

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು

Scanned by CamScanner

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work :-Engaging Gang mens, Silt & Tractor in Bagalagunte Ward No.14

			Est. Cost Rs				40.00	Lakhs	
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	Supply of the Labour Heavy Mazdoor to the required place as per the direction of the engineer in charge Complete as per Specification, and as per direction of Engineer-in charge. Page No LVI Sl No 5 PWD SR 2018-19								
	26 Days x 10 Month=260	Days	26	10	260	10	2600.00		
	per day 10 Mazdoor 260x10=2600						2600.00	446.20	1160120.00
2	Tractor 50 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work (PWD SR 2018-19, P-XLVIII, It.No.20)							Days	
	26 Daysx10 Month=260	Days	26	10	1		260.00		
	per day 1 Tractor						260.00	2129.00	553540.00
3	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work (PWD SR 2018-19, P-XLVIII, It.No.23)							Days	
	55 Days x 1No	Days	55	1			55.00	5695.00	313225.00
4	Removing B.S. slab of drain and stacking with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work..(PWD SR 2018-19, Page No.27, Item No. 5.32)							Sqm	
	at Selected Roads	Sqm	1	2690.00	0.90		2421.00		
							2421.00	104.94	254060.00
	Basic Rate	99.00							
	Add Area Weightage 6%	5.94							
	Total	104.94							
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 27/ Item No.5.33/ PWD SR 2018-19							Sqm	
		Qty Vide Item No 4					2421.00		
			Deduct 80%				1936.80		
	Basic Rate	105.00					484.20	111.30	53891.00
	Add Area Weightage 6%	6.30							
	Total	111.30							
6	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.								
	For New Slab	Sqm	1	300.00	0.90		270.00		
	Missing Slabs		1	200.00	0.90		180.00		
	Data Rates Approved by CE DZ enclosed						450.00	2208.00	993600.00

Scanned by CamScanner

7	Excavation and removal of silt and silt mix with sand in slushy condition form canal bed including disposing of the same in spoil bank or on canal embankment in layers as directed etc., complete with an initial lead upto 50m (MISR Page No.118, Item No.51)							Cum	
		Sqm	1	2690.00	0.45	0.35	423.68		
							423.68	212.60	90073.00
	Basic rate	107.00							
	Add Area Weightage 6%	6.42							
	Total	113.42							
	Lead upto 5 km	68.80							
	Lead upto 9 km (4*5.76)	23.04							
	Total per cum	7.34							
	Total	212.60							
							Sub Total		3418509.00
8	Tender Premium Charge 5%								170925.00
9	GST Charge 12%								410221.00
10	Miscellaneous and UnforessenCharges								345.00
								Total	4000000.00
(Rupees. Forty Lakhs Only)									

Assistant Engineer
Ward-14

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ನಂ.EE/DD/AS/109/ 19-20 ದಿನಾಂಕ : 17/06/19
ರೂ.Rs 40.00 Lakhs
Rupees Forty Lakhs only
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ:CE/DZ/TS/12/18-19 ದಿನಾಂಕ : 02/02/2019
ರೂ. 40.00 Lakhs/- (Rs. Forty Lakhs only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Scanned by CamScanner